BRUHATH BANGALORE MAHANAGARA PALIKE
DTS

Issued to Sri

TEND NO:
ITEM NO:
Orginal/Duplicate

NAME OF WORK: Providing RCC drain, balance portion of 9th cross, Brindavan nagara in ward no 17

Sl. No	Qty	Description of work	Unit	Tender Rate	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	172.20	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications	cum	135.00	Rupees One Hundred Thirty Five Only
2	172.20	Lead for earthwork and disposal of debris shall be payable at carriage rates by mechanical means including loading and unloading for earthwork (upto 15 kms) complete with all lead & lift & as per the direction of the Engineer-in-charge	cum	81.00	Rupees Eighty One Only
3	25.830	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregtes @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	3884.76	Rupees Three Thousand Eight Hundred Eighty Four and Seventy Six Paise Only
4	12.600	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	cum	3223.80	Rupees Three Thousand Two Hundred Twenty Three and Eighty Paise Only
5	21.000	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	sqm	71.60	Rupees Seventy One and Sixty Paise Only
6	2.520	Providing and laying in position plain cement concrete of mix M15 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation,plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	cum	4409.64	Rupees Four Thousand Four Hundred Nine and Sixty Four Paise Only

DTS Approved:

21/7

Signature of the contractor

Executive Engineer
RRNagara Division
BBMP

Scanned by CamScanner

7	5.800	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @ 0.459cum, with superplasticiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications.	cum	5239.08	Rupees Five Thousand Two Hundred Thirty Nine and Eight Paise Only
8	29.700	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for beams, columns, staircase and roof with M20 RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges)	cum	5639.76	Rupees Five Thousand Six Hundred Thirty Nine and Seventy Six Paise Only
9	36.080	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications	qtl	7323.48	Rupees Seven Thousand Three Hundred Twenty Three and Forty Eight Paise Only
10	1944.400	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls ar any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications	sqm	244.08	Rupees Two Hundred Forty Four and Eight Paise Only
11	305.000	Providing and fixing Pre cast solid concrete kerb stones made our of CC 1:2:4 and finished with CM 1:3 of 450X200X400 mm plastering and finishing cutting etc., complete.	nos	289.44	Rupees Two Hundred Eighty Nine and Forty Four Paise Only
12	63.00	Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.	sqm	20.52	Rupees Twenty and Fifty Two Paise Only
13	63.00	Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering includi	sqm	55.08	Rupees Fifty Five and Eight Paise Only

DTP Approved

Signature of the contractor

Executive Engineer
RR Nagara Division
BBMP

Scanned by CamScanner

14	140.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing cramps complete (Grass Rock	sqm	686.00	Rupees Four Hundred Eighty Six Only
15	140.05	Providing two iron dowering to granite stone slab / granite stone masonry as per specifications	sqm	810.40	Rupees Six Hundred Fifty Three and Forty Paise Only
16	280.00	Providing chamfering edges to stone slab 2.5 cms wide as per specifications (only chamfered length shall be recorded)	sqm	23.35	Rupees Twenty Five and Thirty Five Paise Only

Signature of the Contractor

Executive Engineer
Rajarajeshwarinagara Division
[illegible]